

**CAL POLY SPACE SYSTEMS
[CPSS]**

HYBRID MOTOR TEST FIRING PROCEDURES

Table of Contents

1	Procedure Review Sheet	3
2	Test Authorization Sheet.....	4
3	Roles and Responsibilities	5
4	Safety Callouts and PPE	8
4.1	Initial Safety Callouts (To be read out loud before beginning the procedure).....	8
4.2	PERSONAL PROTECTIVE EQUIPMENT	8
5	Pre-Procedure Activities	8
5.1	TRAILER PREPARATION	8
5.1.1	Power Connections	8
5.1.2	Sensor Connection	8
5.1.3	LabVIEW Initialization.....	9
5.1.4	Compressed Air Connection	9
5.2	MOTOR PREPARATION.....	9
5.2.1	Pre-heater Preparation.....	9
5.2.2	Motor Assembly.....	9
6	Procedure Activies	10
6.1	PRE-IGNITION CHECKLIST	10
6.2	PRE-NITROGEN PURGE	10
6.3	FILL PROCEDURE	11
6.4	Fire Procedure:.....	11
6.5	System Safing	12
7	Post Fire-Procedure Activities	12
7.1	Post-Fire N2 Purge.....	12
8	Off-nominal conditions Procedures	13
8.1	Failure to Ignite.....	13
8.2	N ₂ O Fire Valve Failure After Ignition Grain Activation	14
8.3	Significant N ₂ O Leak	14
8.4	Catastrophic Failure	14
9	Troubleshooting	14
10	Approval	15
11	Appendix A: Nitrous Properties.....	16
12	APPENDIX B: Trailer Valve Schematic	17

1 PROCEDURE REVIEW SHEET

Topic:

Meeting Facilitator:

Summary:

Attendees:

Name	Signature	Name	Signature

Signed: _____ Date _____

(Name of SSO or deputy)

Signed: _____ Date _____

(Advisor)

2 TEST AUTHORIZATION SHEET

Name of Test			
Date		Procedure Class:	I II III
Location			
Description of Test			
Summary of Test Results			
Student Safety Officer Present		Test Conductor	
Test Participants	Name	Signature	

Advisor Signature: _____ Date: _____

Student Safety Officer or Deputy: _____ Date: _____

EHS Signature: _____ Date: _____

Test Conductor Signature: _____ Date: _____

Procedure for Hybrid Motor Test Firing

Purpose: This procedure enables the safe static test firing of hybrid rocket motors.

Description: The process for inspecting components, setting up test systems, pre-fire checks, test firing and post-firing inspection are all included in this document. This procedure contains a safe progression of steps for completing the aforementioned tasks and as such should be followed astutely to ensure nominal testing results. **Only the advisor can approve any “redline” changes to the test procedure.**

3 ROLES AND RESPONSIBILITIES

Role	Responsibilities	Name(s)
Test Conductor/Test Lead (TC)	Conducts the specified test.	
	Assures that all steps of the procedure are followed correctly and completely.	
	Reviews the test procedure with all the participants.	
	Maintains position of command and control during the procedure.	
Safety Officer(SO)	Assures that safety procedures are properly and fully implemented.	
	Assures all nonessential personnel are clear of test area.	
Fire and Sensor Control (FSC)	Operates the ignition circuit, actuated disconnects, and firing valves.	
	Shuts off the ignition circuit and firing valves in the event of an abort.	
	Manages sensors and data acquisition program(s).	
	Controls filling and venting operations.	
Range Safety (multiple)	In radio communication with Test Conductor.	
	Prevents bystanders from approaching the test area.	




Figure 1: Map of Area Around Propulsion Lab

The red area indicates the region where bystanders are not allowed during fill and fire procedures. The numbers signify where range safety is posted. The dark red area is the downrange, restricted area of the propulsion lab, which is the south yard.






Figure 2: Diagram of Restricted, Controlled, and Safe Areas of the Propulsion Lab.
 The restricted area is in the south yard



Propulsion Lab



4 SAFETY CALLOUTS AND PPE

4.1 Initial Safety Callouts (To be read out loud before beginning the procedure)

1. Unless otherwise specified in Off-Nominal Procedures, no-one may enter the Controlled or Restricted areas of the test cell during the Fill and Fire procedures (6.3 and 6.4, respectively). No one may enter the Restricted Area of the test cell during the Procedure Activities (6) and the Post Fire-Procedure Activities (7).
2. Everyone present is encouraged to have a questioning attitude, and should be on the lookout for potential hazards. Everyone present has the responsibility to call an all-stop in the event that he or she perceives something as unsafe.
3. The controlled area in the prop lab can only be entered when the system does not have nitrous oxide under pressure and when no liquids or gasses are flowing in the system. The controlled area at the trailer can only be approached when no liquids or gasses are flowing in the system. At no point during Fill Procedure (6.3) and Fire Procedure (6.4) will anyone enter the Restricted area of the test cell. Authorized personnel can only enter the Controlled area when specifically allowed in the Off-Nominal Procedures (8), or with the permission of the Advisor in special circumstances.
4. The Nitrogen bottle on the trailer will be referred to as the N₂ Bottle. The nitrous oxide bottle on the trailer will be referred to as the N₂O bottle. The nitrous oxide tank at the test stand will be referred to as the nitrous tank.
5. Range Safety will call “hold, hold, hold” if anyone enters the test range during sections 6.3 (Fill Procedure) and 6.4 (Fire Procedure).
6. Any participant may call “hold, hold, hold” if an anomaly is noticed or the situation becomes unsafe.

4.2 PERSONAL PROTECTIVE EQUIPMENT

1. All participants are required to wear ear plugs or ear muffs during section 6.4 (Fire Procedure).
2. All participants must wear long pants and close toed shoes.
3. All participants must wear safety glasses during this procedure when working on or around equipment.
4. The test lead must wear a face shield when in close proximity to the launch trailer or test stand. The launch trailer can be approached by only the test lead as specified in sections 6 and 7.
5. Designated participants must wear nitrile gloves and a face shield when handling the pre-heater.

5 PRE-PROCEDURE ACTIVITIES

Test Stand is located inside the prop lab walls and is connected to the trailer via long hoses and wires. The trailer is located outside the prop lab. The test stand contains the motor, fire valve and nitrous tank. The trailer contains the test computer, N₂O bottle and N₂ bottle. The task list associated with this test must be completed prior to beginning this section.

5.1 TRAILER PREPARATION

5.1.1 Power Connections

- _____ 1. Verify 12-Volt Trailer Battery is charged and connected
- _____ 1. Connect Trailer Computer to power
- _____ 2. Connect the Launch Box and Trailer Computer

5.1.2 Sensor Connection

- _____ 1. Verify Sensors are connected to the Black Box on the trailer

5.1.3 LabVIEW Initialization

- _____2. Verify the Trailer Computer is on and LabVIEW is running
- _____3. Verify the Trailer Computer is connected to the Data Acquisition System
- _____4. Verify all relevant instruments connected and data is shown in LabVIEW

5.1.4 Compressed Air Connection

- _____1. Attach Trailer to compressed air supply of 80 psi or higher

5.2 MOTOR PREPARATION

*This step must be completed in a well ventilated area (in the high bay) on a surface that is fire resistant. Motor assembly must be performed with nitrile gloves, safety glasses, and a face shield. **If the preheater ignites during the following steps, vacate the area and allow 5 minutes for the smoke to dissipate.***

5.2.1 Pre-heater Preparation

- _____1. Motor assembler must ground the propellant container and themselves.
- _____2. Remove a propellant grain from the propellant container and record its linear density (mass/length).
- _____3. Cut the propellant grain so it has a mass of $12\text{g} \pm 1\text{g}$. **Actual mass:** _____
- _____4. Peel away the liner of the cut section
- _____5. Remove the e-match from the propellant container and extend the leads if necessary. Leads must be about 22 inches long.
- _____6. Using electrical tape, attach the e-match to the inner surface of the propellant grain.

5.2.2 Motor Assembly

- _____1. Place the pre-heater grain at the forward end of the fuel grain, and use a small amount of 5-minute epoxy to affix the pre-heater to the fuel grain
- _____2. Once cured, slide the grain into the combustion chamber casing.
- _____3. Verify nozzle O-ring is in place and insert the nozzle so the pressure port lines up with the port in the combustion chamber casing wall.
- _____4. Thread aft chamber cap onto the motor and tighten so the port in the cap lines up with the port in the chamber wall.
- _____5. Thread forward chamber cap onto the motor and tighten.
- _____6. Thread the pressure transducer line into the nozzle and tighten. Teflon/PTFE tape should be used on threads.
- _____7. Attach motor to the fire valve assembly and tighten threads.
- _____8. Affix motor to the test stand bearing plates using four U-bolts.
- _____9. Attach pressure transducer to the nozzle.
- _____10. Verify igniter leads are not connected to the Lunch Box. Touch leads together and connect to the motor.

Motor is now assembled. Once clear of the motor, assembler can remove face shield.

6 PROCEDURE ACTIVITIES

This is the beginning of the test fire procedure activities. Essential personnel are those with assigned positions in the procedure and may enter the test cell when instructed during the procedures. All non-essential personnel must remain in the control room or designated safe area. Once the Test Conductor closes the control room door, permission from the test conductor is needed to use the doors.

6.1 PRE-IGNITION CHECKLIST

- _____ 1. Turn cameras(s) to Wi-Fi mode and connect to wireless device. Web-cam cameras should be verified operating at this time. Begin livestream now if applicable.
The following verifications will be made visually by the test lead
- _____ 2. Verify N₂O Fill valve actuation
- _____ 3. Verify N₂ to N₂O valve actuation
- _____ 4. Verify N₂ Fill valve actuation
- _____ 5. Verify Dump valve actuation
- _____ 6. Verify Vent solenoid activation
- _____ 7. Verify N₂O quick disconnect operation
- _____ 8. Verify disconnects do not physically interfere with pressure transducers when disconnecting
- _____ 9. Verify Fire valve actuation

6.2 PRE-NITROGEN PURGE

The following verifications will be made visually by the test lead

- _____ 1. Verify N₂ Fill is CLOSED
- _____ 2. Verify N₂ regulator is set to MINIMUM
- _____ 3. Verify N₂ to N₂O valve is CLOSED
- _____ 4. Verify N₂O fill is CLOSED
- _____ 5. Verify Dump valve is CLOSED
- _____ 6. Verify N₂O Bypass is OPEN
- _____ 7. Connect regulator to N₂ bottle
- _____ 8. Open N₂ tank valve and adjust N₂ tank regulator to 100psi
- _____ 9. Open N₂ to N₂O valve
- _____ 10. Open N₂O Fill valve until pressure stabilizes
- _____ 11. Open Vent Solenoid for 10 seconds and close
- _____ 12. Close N₂O Fill valve
- _____ 13. Open N₂ Fill Valve until pressure stabilizes
- _____ 14. Open Vent Solenoid for 10 seconds and close
- _____ 15. Close N₂ Fill Valve
- _____ 16. Close N₂ to N₂O valve
- _____ 17. Set N₂ regulator to 800 psi
- _____ 18. Open N₂O Fill Valve
- _____ 19. Open Dump valve until N₂O line and Oxidizer Tank are depressurized
- _____ 20. Close N₂O Fill Valve
- _____ 21. Close Dump Valve

6.3 FILL PROCEDURE

- _____ 1. Visually Verify N₂O Fill valve is closed
- _____ 2. Connect N₂O fill line to N₂O tank
- _____ 3. Assign Range Safety personnel to positions specified
- _____ 4. **Test is now live. Only Authorized personnel are allowed within Controlled areas as specified by the procedure.**
- _____ 5. Open N₂O Tank valve
- _____ 6. Hold tank weight in LabVIEW
- _____ 7. Begin recording with GO-PRO(s) or range cameras
- _____ 8. Open N₂O Fill valve
- _____ 9. Open Vent valve periodically to maintain pressure by venting system when pressure is above equilibrium pressure for the current temperature. (Refer to nitrous data sheet in Appendix A)
- _____ 10. Close Fill valve when the tank weight readout shows the desired weight. Note: 0.2lb of N₂O is in the Fill line which will be disconnected.
- _____ 11. Disconnect Fill assembly
- _____ 12. Open N₂ Fill valve

6.4 Fire Procedure:

This section will be read aloud before proceeding to ensure everyone present understands what will occur.

- _____ 1. Attach igniter leads
 - i. Touch both igniter leads to ground before connecting
- _____ 2. Verify range safety is in position
- _____ 3. Begin LabVIEW data recording
- _____ 4. Put on Ear Protection
- _____ 5. Test Conductor begins ten second countdown over the radio.
 - i. Keep radio clear at T- 5 seconds so that range safety can notify the Test Conductor in the event of an anomaly.
- _____ 6. Ignite preheater grain
- _____ 7. Confirm through GO-PRO image or test webcam that preheater grain has lit and wait 8 seconds. If pre-heater grain does not light, enter Off-Nominal Procedure 8.1
- _____ 8. Open Fire valve (This starts the flow of nitrous into the combustion chamber and will be very loud). If Fire valve does not open, enter Off-Nominal Procedure 8.2
- _____ 9. Wait for confirmation that the nitrous is depleted. (The thrust load cell should read near zero and the noise level should drop significantly from the peak. The sound of nitrogen gas flowing may still be audible)
- _____ 10. Close N₂ Fill valve
- _____ 11. Wait 10 seconds
- _____ 12. Close Fire valve

6.5 System Safing

Lines are depressurized when the flow of gas from the dump valve is no longer audible. Ear protection may be removed at this time.

- _____ 1. Open N₂O Dump Valve until N₂O line is depressurized
- _____ 2. Close N₂O Dump Valve
- _____ 3. Close N₂O Tank Valve
- _____ 4. Close N₂ Tank Valve
- _____ 5. Open N₂O Dump Valve
- _____ 6. Open N₂O Fill Valve
- _____ 7. Open N₂O to N₂ Valve and wait until lines are depressurized
- _____ 8. Close N₂O to N₂ Valve
- _____ 9. Close N₂O Fill Valve
- _____ 10. Close N₂O Dump Valve

*The Test Conductor may enter the Controlled area as specified in the procedure. **Absolutely no one else may enter the Restricted or Controlled areas of the test cell.***

7 POST FIRE-PROCEDURE ACTIVITIES

7.1 Post-Fire N₂ Purge

- _____ 1. Verify N₂ Fill is CLOSED
- _____ 2. Set N₂ Regulator to MINIMUM
- _____ 3. Verify N₂ to N₂O valve is CLOSED
- _____ 4. Verify N₂O fill is CLOSED
- _____ 5. Verify Dump valve is CLOSED
- _____ 6. Verify N₂O Bypass is OPEN
- _____ 7. Open tank valve and adjust regulator to 100psi
- _____ 8. Open N₂O to N₂ valve
- _____ 9. Close N₂O to N₂ valve
- _____ 10. Open Dump valve until system depressurizes
- _____ 11. Close Dump valve
- _____ 12. Open N₂ Fill Valve until pressure stabilizes
- _____ 13. Open Vent Solenoid for 10 seconds and close
- _____ 14. Manually close N₂ tank valve
- _____ 15. Open Vent Solenoid until Oxidizer Tank is depressurized
- _____ 16. Close N₂ Fill valve
- _____ 17. Range Safety may be recalled to the Control Room
- _____ 18. **Announce "ALL CLEAR"**

All areas of the Propulsions Lab are now safe to enter. Required PPE must be worn until procedures have concluded and all systems have been disassembled and stored.

8 OFF-NOMINAL CONDITIONS PROCEDURES

The Controlled area can only be entered when the system does not have nitrous oxide under pressure and when no liquids or gasses are flowing in the system. At no point between 6.3 Fill Procedure and 6.4 Fire Procedure may anyone enter the Restricted area of the test cell.

8.1 Failure to Ignite

Failure to ignite means that the pre-heater grain did not ignite.

- _____ 1. Ensure firing circuit is armed and proceed back to 6.4.1. If the second attempt fails, continue below.
- _____ 2. Disable fire valve circuit
- _____ 3. Check continuity on igniter from relay and work through system to igniter
- _____ 4. If continuity check finds no faults, disconnect ignition leads and ensure correct functioning of fire circuitry. If there is a fault, attempt to repair the fault if personnel only need to enter allowable areas to fix the fault. If the fault cannot be fixed, proceed with the following until the range is considered safe.
- _____ 5. If no problems are detected, the igniter is assumed defective, and a new igniter must be placed in motor
- _____ 6. Notify Range Safety that the nitrous tank will be vented
- _____ 7. Ensure Fill Valve circuit is not armed.
- _____ 8. Open Dump Valve until N₂O line is depressurized
- _____ 9. With everyone but Range Safety in the Control Room, activate the vent valve until tank pressure is zero and wait five minutes (so the nitrous can dissipate)

The Test Conductor may now enter the Controlled Area, but may not enter the Restricted area

- _____ 10. The Test Conductor will grab the e-match wire with a grabber, and pull it out through the nozzle
- _____ 11. The Test Conductor and the Advisor will then inspect the e-match to see if it fired
- _____ 12. If the e-match did not fire, the range is considered safe, and the combustion chamber may be disassembled
- _____ 13. If the e-match did fire, the pre-heater grain is considered dangerous, (it was given enough energy to potentially fire, but did not, so it must be made safe to handle)
- _____ 14. The Test Conductor, while standing in the Controlled Area, will point a hose, which will be held by a pole, into the nozzle mouth
- _____ 15. Turn on the hose, and rinse for two minutes, to ensure that the pre-heater grain is at a low enough temperature to be considered safe to handle
- _____ 16. Turn off the hose
- _____ 17. The range is now considered safe, and the combustion chamber may be disassembled

8.2 N₂O Fire Valve Failure After Ignition Grain Activation

- _____ 1. Disable fire valve circuit
- _____ 2. Check wiring in the test cell control room.
- _____ 3. Ensure sufficient air pressure to fire valve actuator
- _____ 4. Reattempt opening of fire valve. If valve does not open, the test is aborted and the following items will safe the system.
- _____ 5. Notify Range Safety that the nitrous tank will be vented
- _____ 6. Open Vent solenoid to depressurize oxidizer tank and wait 5 minutes (so the nitrous can dissipate)
- _____ 7. Proceed to 7.1 (Post Fire N₂ Purge)
- _____ 8. Troubleshoot fire valve as necessary

8.3 Significant N₂O Leak

- _____ 1. Depressurize leaking line/vessel using appropriate vent.
- _____ 2. Proceed to 6.5 (System Safing) to safe system. Continue with section 7.1. Once completed return to the following.
- _____ 3. Disassemble leaking connection and inspect for cause of leak
- _____ 4. Reassemble connection, ensure to torque to appropriate specification

8.4 Catastrophic Failure

- _____ 1. Immediately shut any open valves in the N₂O systems starting with the remotely actuated valves.
- _____ 2. Check for visible fire. (The GO PRO and test webcam should still be running) If there is a fire or anyone is injured call 911. Evacuate the control room if safe and necessary to do so.
- _____ 3. Seek guidance from Advisor and/or other R.P.

9 TROUBLESHOOTING

In the event that an off-nominal condition occurs that prevents continuation of the procedures but is not covered in Section 8, the following troubleshooting procedures shall be followed.

- _____ 1. De-energize any electrical control circuits via safety switches
- _____ 2. Identify sources of off-nominal condition
- _____ 3. Disconnect connectors to ignition charge if connected
- _____ 4. Depressurize Oxidizer tank if personnel need to enter the controlled area
- _____ 5. If the problem is electrical, check electrical connects with a multimeter
- _____ 6. When problem is resolved the procedures may be restarted with an O.K. from the advisor.

10 APPROVAL

Date:

Advisor: Dr. Ian Johnson

Date: 2/18/16

Additional Signoff: Tom Featherstone

11 APPENDIX A: NITROUS PROPERTIES

Thermophysical properties of nitrous oxide on the saturation line for temperature in degree Celsius

t °C	p kPa	$\rho(l)$ kg/m ³	$\rho(g)$ kg/m ³	$h(l)$ kJ/kg	$h(g)$ kJ/kg	$\Delta_{\text{vap}}h$ kJ/kg
-90.82	(87.73)	1222.8	(2.613)	(-474.)	(-96.8)	(377.)
-90	(92.29)	1220.6	(2.738)	(-473.)	(-96.3)	(377.)
-88.46	101.325	1216.3	(2.987)	(-470.)	(-95.4)	375.
-85	124.2	(1206.7)	(3.609)	(-464.)	(-93.3)	371.
-80	164.2	(1192.7)	(4.680)	(-455.)	(-90.4)	365.
-75	213.6	(1178.3)	(5.982)	(-446.)	(-87.6)	359.
-70	273.6	(1163.7)	(7.546)	(-438.)	(-85.0)	353.
-65	345.7	(1148.8)	(9.406)	(-429.)	(-82.5)	346.
-60	431.5	(1133.6)	(11.60)	(-420.)	(-80.2)	340.
-55	532.3	(1118.0)	(14.16)	(-411.)	(-78.1)	333.
-50	649.9	(1102.0)	(17.14)	(-402.)	(-76.1)	326.
-45	785.8	(1085.6)	(20.58)	(-392.)	(-74.4)	318.
-40	941.7	(1068.8)	(24.53)	(-383.)	(-72.9)	310.
-35	1119.	(1051.4)	(29.05)	(-374.)	(-71.6)	302.
-30	1321.	1033.4	34.22	(-364.)	(-70.5)	294.
-25	1547.	1014.8	40.11	(-355.)	(-69.8)	285.
-20	1801.	995.4	46.82	(-345.)	(-69.3)	276.
-15	2083.	975.2	54.47	(-335.)	(-69.2)	266.
-10	2397.	953.9	63.21	(-325.)	(-69.5)	255.
-5	2744.	931.4	73.26	(-315.)	(-70.3)	244.
0	3127.	907.4	84.86	(-304.)	(-71.7)	232.
5	3547.	881.6	98.41	(-293.)	(-73.7)	219.
10	4007.	853.5	114.5	(-281.)	(-76.6)	204.
15	4510.	822.2	133.9	(-269.)	(-80.6)	188.
20	5060.	786.6	158.1	(-255.)	(-86.2)	169.
25	5660.	743.9	190.0	(-241.)	(-94.4)	147.
30	6315.	688.0	236.7	(-224.)	(-108.)	117.
35	7033.	589.4	330.4	(-203.)	(-138.)	64.9
36.42	7251.	452.	452.	(-200.)	(-200.)	0

12 APPENDIX B: TRAILER VALVE SCHEMATIC

